



Grand Bras
St. Andrew's
Tel. # (473) 520 3000

info@simplypureagroprocessing.com
www.simplypureagroprocessing.com

SIMPLY PURE AGROPROCESSING

WHO ARE WE?

Simply Pure Agro processing (SPA) is a locally owned and operated Limited Liability Company owned and operated by Grenadians. The company has been operating for the past 5 years supplying soursop fruit and pulp to the U.S. and Trinidad markets. Simply Pure Agroprocessing is owned and managed by Grenadians Marlon St. Louis and Dawn Williams. Both parties are young business entrepreneurs with a combined 25 plus years of business and professional experience.

Subject: Item for the Irrigation System – Simple Pure Agriculture, Grenada

Request for Quotation (RFQ)

Date: 2nd September 2024

To Whom It May Concern,

Subject: Request for Quotation for Drip Irrigation System Materials

Dear Supplier,

Simple Pure Agroprocessing (SPA) is pleased to announce that we have partnered with the Caribbean Agricultural Research and Development Institute (CARDI) to implement a project aimed at enhancing the irrigation systems for sour sop tree cultivation in Belair, St. Andrew, and Rose Hill, St. Patrick's. As part of this initiative, we are seeking quotations from reputable suppliers for the procurement and delivery of irrigation system materials.

We invite your esteemed company to submit a comprehensive quotation for the following Bill of Materials required for the "SPA 50 tree system (Drip Only)." We are

planning to purchase materials for 30 such systems. Each system should include the listed components per kit:

Bill of Materials for SPA 50 Tree System (Drip Only)

Name	Quantity
3/4" Hose Thread Filter	1
Barb Tubing Coupling - Size: 1/4"	100
Barb Tubing Tee - Size: 1/4"	100
Pro Punch - 1/4" Hole	1
Goof Plug - Size: 1/4"	50
Perma-Loc Tubing Coupling - Size: 3/4"	2
Perma-Loc Tubing x 3/4" FHTS Adapter	1
Perma-Loc Tubing End Cap - Size: 3/4"	1
1/4" Polyethylene Dripline - 12" Emitter Spacing	4
1/4" Polyethylene Tubing - 100' Length	3
3/4" Hose Thread Pressure Regulator - 25 PSI	1
3/4" Polyethylene Tubing - 500' Length	1
Brass Vacuum Breaker - 3/4" GHT	1
6" Heavy Duty Wire Staple	150

Additional Components Required

Polyethylene Mainline Tubing

- **Size:** 3/4" (0.820" ID x 0.940" OD) - Length: 500'
- **Quantity:** 25 extra units

Head Assembly Units

- **Quantity:** 10 units (each set includes the following components compatible with the above list):
 - Hose End Irrigation Timer
 - Hendrickson Bros J10 Vacuum Breaker (Backflow Preventer)
 - 3/4" GHT Canister Filter
 - Senninger 3/4" GHT 25 PSI Pressure Regulator
 - 3/4" FHTS x 1/2" Poly Tubing Adapter

Solar Charged Pumping Units

- **Description:** Solar Well Pump Kit with Battery Backup, 12V Solar Water Pump + 120W Solar Panel Kit + 10Ah Battery for Well, Irrigation, Filling Water Tank
- **Quantity:** 1 unit

We request that the products be delivered to our office in Grand Brass, St. Andrew's. Please include delivery costs, lead times, and payment terms in your quotation.

We look forward to receiving your detailed quotation by [Insert Deadline Date]. Should you have any questions or require further clarifications, please do not hesitate to contact us.

Thank you for considering this request.

Sincerely,

Marlon St. Louis
Simple Pure Agroprocessing
info@simplypureagroprocessing.com
www.simplypureagroprocessing.com

We need complete quotation and guaranteed delivery within 2 to 3 weeks.

Items Needed for the Sour Sop SPA Drip System Kit:



Item that must be included for the 10 head assembly systems.

Items Needed for the Sour Sop SPA Drip System Kit:



Bill of materials for the construction of the tank placement facility.

Item	Description	Cost Estimate
Cements	15 bags	\$900.00
Gravels	2 small truck loads	\$600.00
Sand	1 small truck load	\$560.00
Bricks 8 inch	100 units	\$500.00
		EC \$2,560

**** Job to construct the hosting space for tanks EC\$1,500.00**